

## Work specifications

## Annexure -A

sl no	Specifications
1	P.C.C. Chipping & cleaning of existing road 290m <sup>2</sup>
2	Cement concrete(1:3:6) with stone chips (20mm size) excuding shuttering & reinforcement with Pakur stone chips
3	Supplying & laying 20mm designer chequered tiles of any shade of approved quality as per is 1237:1980 laid in patterns as directed in footpath necessary underlay 25mm thick average cement mortar (1:3) complete in all respect with all labour & materials. 290m <sup>2</sup>